



Republic of the Philippines
DEPARTMENT OF HEALTH
PHILIPPINE CHILDREN'S MEDICAL CENTER

Quezon Avenue, Quezon City 1100
website: www.pcmc.gov.ph email: officeofthedirector@pcmc.gov.ph
Trunk Line: 8588-9900 to 20 Direct Line: 8924-6601

NOTICE OF AWARD
NOA-2024-098

MLS JC CONSTRUCTION SERVICES

JVA Mindanao Laboratory Services

Davao St., Aluba Subd. Macasandig,
Cagayan de Oro City, Misamis Oriental
Tel. No.: (063) 850-0092
Email Add: mlsjcconstruction@yahoo.com

Dear Sir / Madam:

This is to inform you that based on the result of the conducted Public Bidding for the project stated below under Invitation to Bid No. IB-2024-051 as per BAC Resolution No. R2024-07-389, your proposal was found to be responsive.

QTY	UNIT	ITEM DESCRIPTION	TOTAL COST
1	lot	Supply, Delivery, Installation, Testing and Commissioning of the following: One (1) unit 500 KVA Industrial Electric Continuous Power Generator Brand/Model: WELLPOWER WP-C500GF One (1) unit 3200AT Automatic Transfer Switch (ATS) Brand/Model: SCHNEIDER ELECTRIC ASCO 7000 SERIES (see Annex "A" for detailed specifications)	Php49,989,999.91

You are hereby required to provide on or before 09 AUG 2024 the Performance Security in either of the following form:

Kindly disregard and report any form of solicitation using the name of the Executive Director and/or the PCMC. These unsanctioned requests are unlawful and will not be tolerated.



MLS JC CONSTRUCTION SERVICES JVA Mindanao Laboratory Services

One (1) Lot Supply, Delivery, Installation, Testing and Commissioning of One (1) set 500 KVA Industrial Electric Continuous Power Generator and 3200AT Automatic Transfer Switch (ATS)

FORM OF PERFORMANCE SECURITY	AMOUNT OF PERFORMANCE SECURITY (Equal to Percentage of the Total Contract Price)
a) Cash or cashier's/ manager's check issued by a Universal or Commercial Bank	Five percent (5%)
b.) Bank draft/guarantee or irrevocable letter of credit issued by a Universal or Commercial Bank: Provided, however, that it shall be confirmed or authenticated by a Universal or Commercial Bank, if issued by a foreign bank	Php2,499,500.00
c) Surety bond callable upon demand issued by a surety or insurance company duly certified by the Insurance Commission as authorized to issue such security.	Thirty percent (30%) Php14,996,999.97

Failure to provide the Performance Security shall constitute sufficient ground for cancellation of the award and imposition of penalties/ forfeiture corresponding to the Bid Security posted.

Very truly yours,


SONIA B. GONZALEZ, MD, MScHSM, MPM
 Executive Director 

Conforme:

This is to certify that the company has authorized me to accept this award, sign all related documents and hold the company bound by rules and laws applicable thereto.

 Authorized Signatory (Signature over printed name)

Designation

Date

Kindly disregard and report any form of solicitation using the name of the Executive Director and/or the PCMC. These unsanctioned requests are unlawful and will not be tolerated.



MLS JC CONSTRUCTION SERVICES JVA Mindanao Laboratory Services

QTY	UNIT	ITEM DESCRIPTION
1	lot	One (1) Lot Supply, Delivery, Installation, Testing and Commissioning of One (1) set 500 KVA Industrial Electric Continuous Power Generator and 3200AT Automatic Transfer Switch (ATS) Total Cost = Php 49,989,999.91
		I. One (1) unit 500 KVA Industrial Electric Continuous Power Generator
		Brand/Model: WELLPOWER WP-C500GF
		Unit Cost = Php 18,000,000.00
		A. Main Equipment
	a	Equipped with brand new alternators; four (4) Poles 24VDC Battery, brushless type, self-exciting, self-regulating with class H insulation
	b	PRIME POWER/CONTINUOUS DUTY : Continuous duty cycle
	c	TURBOCHARGED AIRCOOLED
	d	Electronic governor
	e	Upgradable controller: SMARTGEN
	f	Low sound level of not more than 75 decibels at seven (7) meters
	g	Silent Canopy containerized type
	h	Six (6) cylinders, four (4) cycle diesel engine, in-line, four (4) stroke generating set: CUMMINS ENGINE KTA19-G3
	i	Power output: 400VAC line to line and 230VAC line to neutral
	j	Voltage output ratings: 400VAC line to line, 230VAC line to Neutral, 3 phase, 60Hz, 500KVA
	k	Safety power breaker
	l	Mechanical parts are of heavy duty durable type
	m	Equipment is maintainable and serviceable
	n	Will provide circuit breakers
	o	Will provide as built plans
		B. Accessories:
	a	Rechargeable Automotive Battery 8D
	b	Separate on-line charger unit for 24VDC Battery
	c	KRAMPITZ TTE-XL-STANDARD 2500 LITERS DAY TANK Diesel fuel day tank with loading pump, 2500 liters capacity
		C. Consumables:
	a	Will provide 2,500 liters diesel fuel
		D. Warranty:
	➤	Three (3) years warranty on services, parts, accessories and software
	➤	Semi-annual preventive maintenance or standard maintenance provided by manufacturer's manual
		II. One (1) unit 3200AT Automatic Transfer Switch (ATS)
		Brand/Model: SCHNEIDER ELECTRIC ASCO 7000 SERIES
		Unit Cost = Php 8,000,000.00

MLS JC CONSTRUCTION SERVICES JVA Mindanao Laboratory Services

QTY	UNIT	ITEM DESCRIPTION
		A. Main Equipment
	a	Automatic transfer switch, with ampere trip (AT) rating of three thousand two hundred (3200) in NEMA1, powder coated two-door cabinet, with ATS on first door and on second door are the three pole color-coded RYBN extended bus bars with complete lugs and spare holes. With copper terminal blocks with lugs for grounding connection. Blank front covers will be supplied with hinges
	b	With mechanical interlock
	c	Air Circuit Breaker type
	d	ATS integration with the GENSET System
		Key Features:
		Protection disabled feature
		KW overload protection
		Load switching (load shedding)
		Independent earth fault trip
		Remote SCADA monitoring
		Fully configurable via configuration PC Software
		Output monitoring/recording devices will be installed at load side of ATS to monitor: KW, KVA, V, A, Hz, etc. and generates energy report with automated and customized format in excel form approved by PCMC
		User RS 485 cable communications
		USB and/or WIFI connectivity
		Back up in real time clock
		ATTACHED ASCO PERFORMANCE TESTING FOR TRANSFER SWITCHES AND UL 1008 TRANSFER SWITCH WITHSTAND AND CLOSING RATINGS Can automatically transfer load between the main power and the emergency power (generating set) with or without operator When the main power fails or voltage drops below 80% of normal voltage, the ATS will start the emergency power generating set after a preset time of 0 to 10 seconds, preferred is 7 seconds to energize and transfer to emergency power generating set. Contrary, when the main power recovers normal, the ATS will transfer the load from the emergency power to main power, and then stop the emergency power after the preset cooling down time preferred is 3 minutes to stop and standby mode
		Laptop with licensed software, latest edition, for real-time monitoring/recording output at Genset tender area, with hub for intranet connection
		Brand/Model: DELL 13th Generation Intel® Core™ i7-13620H Processor (24MB Cache, up to 4.9GHz) XPS15
	e	Mechanical parts are of heavy duty durable type
	f	Equipment is maintainable and serviceable
	g	Will provide circuit breakers
	h	Will provide as built plans

MLS JC CONSTRUCTION SERVICES JVA Mindanao Laboratory Services

QTY	UNIT	ITEM DESCRIPTION
		B. Warranty:
		➤ Three (3) years warranty on services, parts, accessories and software
		➤ Semi-annual preventive maintenance or standard maintenance provided by manufacturer's manual
		III. With duly notarized certificate from Distributor - MLS JC CONSTRUCTION SERVICES JVA Mindanao Laboratory Services
		<i>Certifies that:</i>
		i. That parts, accessories and consumables are readily available at MLS JC CONSTRUCTION SERVICES, Philippine service center/s for a period of five (5) years after the warranty period;
		ii. That it has available competent in-house technical specialists in handling and providing technical support as well as maintenance of the equipment being offered;
		iii. That it will conduct training for proper operation and maintenance to end-users of the equipment upon delivery; and
		iv. That it will provide replacement/back-up unit while the delivered unit is being repaired.
		IV. With duly notarized certificate from Principal Manufacturer - JIANGSU WELLPPOWER GENERATOR CO., LTD.
		<i>Certifies that:</i>
		i. All the terms and conditions stated in the bidding documents per IRR of RA 9184 and corresponding contract for the project shall be honored by Jiangsu Wellpower Generator Co., Ltd., including in the event that a change of dealership will occur during the duration of the contract up to the warranty and preventive maintenance period;
		ii. The expected useful life of the equipment is thirty (30) years under normal use with 5-6 hours everyday use;
		iii. Guarantee on availability of all spare parts, accessories and consumables for the next five (5) years from testing, commissioning, acceptance and delivery;
		iv. That it has competence in handling and providing technical support as well as maintenance of the equipment being offered; and
		v. Consumer guidelines regarding disposal of the equipment:
		One (1) unit 500 KVA Industrial Electric Continuous Power Generator
		Exchange of Gensets from the distributor, in return for the purchased unit after end of useful life at reasonable prices (see attached certification).
		One (1) unit 3200AT Automatic Transfer Switch (ATS)
		Disposal of ATS can be associated with recycling. Disposal of this product, solutions and any by-products should at all times comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements (see attached certification).
		Renovation and Other Infra Costs = Php 23,989,999.91
		CONFORME to all the details contained in the attached Terms of Reference (TOR)

MLS JC CONSTRUCTION SERVICES JVA Mindanao Laboratory Services

QTY	UNIT	ITEM DESCRIPTION
		V. DELIVERY PERIOD: One Hundred Twenty (120) calendar days upon receipt of Purchase Order/Notice to Proceed

Conforme:

Authorized Signatory (Signature over printed name)

Designation/Position

Date _____